


NOTES:

1. ALL WORK SHALL BE SUPERVISED BY AN ISA CERTIFIED ARBORIST.
2. NO ROOTS GREATER THAN 1" SHALL BE CUT WITHOUT REVIEW BY ARLINGTON COUNTY URBAN FORESTER.
3. EXCAVATION SHALL BE NOT MORE THAN MINIMUM NEEDED TO ACHIEVE REQUIRED FINAL GRADE
4. ALL EXCAVATION SHALL BE BY SSAT AND/OR BY HAND TO MINIMIZE ROOT DAMAGE AS DIRECTED BY CERTIFIED ARBORIST.
5. WORK SHALL NOT DAMAGE TREE TRUNK, LIMBS OR ROOTS TO REMAIN.

ALL SITE PREP/GRADING TO BE DONE USING AIR SPADE TO MINIMIZE ROOT DAMAGE. ALL WORK SHALL BE SUPERVISED BY CERTIFIED ARBORIST.



TREE SENSITIVE CONCRETE SIDEWALK

311300.IINS

N.T.S.

